Sl. No.	Names of materials, etc.	Unit	Quantity
3	Earthing the lead sheathing of the circuits in 2 places including lighting distribution (these should be independent of the earthing against item 8 of Part I)		
	Part IV—Lighting Fixtures.		
1	Supplying, fixing and wiring B. C. lamp holders with stout ceiling plate, all nickel plated complete with 8″×4¼″ opal round globes, nickel plated gallery, etc., using necessary accessories	No.	26
2	Do do with 10″ round opal globes nickle plated gallery, etc., as per above	,,	1
3	Supplying, fixing and wiring pendants ⅝″ braized conduits, silver lac finish, complete with stout brass ceiling plate, B. C. lamp holder, 2′ to 3′ long, complete with 10″×5″ white opal shades, using No. 3/036 SWG. insulated wire and accessories	,,	18
4	Supplying, fixing and wiring bulk head fittings with cast iron enamelled reflector, etc., as above	,,	3
5	Do do 6″×½″ O. C. brackets complete with O.C.B.C. lamp holder, 10″×5″ white opal shade as per specification above	,,	20
6	Do do for china counter weights, complete with porcelain 2 plate ceiling rose, ring, pulley and guide, lead shots, flexible cord, etc., equipped with 'benflux' fittings complete with shade, etc., using necessary accessories, as per specification above	,,	2
7	Supplying and fixing 'MYSORE' lamps, 150 watts, 230 volts, B. C. gas filled clear	,,	1
8	Do do do 100 watts clear	,,	26
9	Do do do 100 watts internally frosted	,,	2
10	Do do do 60 watts do	,,	41

M. M. ALI KHAN,
Superintendent.

MYSORE STATE RAILWAY.

DISTRICT ENGINEER'S OFFICE, MYSORE.

Abstract Notification dated 13th January 1940.

The attention of the public is invited to the detailed Notification dated 4th January 1940, published in the *Mysore Gazette*, dated 11th January 1940, on pages 79 to 81 of Part VI, regarding deviation of Railway line for improving curves and grades between miles 221–7 and 222–3, Bangalore-Mysore Section. The last day of receiving tenders is up to 3 P.M. on Monday the 29th January 1940.

Intending tenderers will please note the following additions in the Schedule :—

II. Constructing 1-6′ Slab Top.

Item No. 11.—Loading departmental stones and slabs into Ballast Train and unloading the same and conveying them to site with a lead up to 15 miles
Approximate quantity 4,357 c.ft. Unit 100 c.ft.

Item No. 12.—Coursed rubble size stone masonry first class with the above departmental stones in lime mortar or 1 in 6 cement mortar
Quantity 4,357 c.ft. Unit 100 c.ft.

Abstract Notification dated 13th January 1940.

The attention of the public is invited to the detailed Notification dated 6th January 1940, published in the *Mysore Gazette*, dated 11th January 1940, on pages 82 to 86 of Part VI, regarding providing a Crossing Station at Nagenahalli at mile 291–11 on Bangalore-Mysore Section. The last day of receiving tenders is up to 3 P.M. on Wednesday the 31st January 1940.

D. V. NARASIMHA RAO,
District Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, S. T. RAILWAY CONSTRUCTION, SAGARA.

Notification dated 13th January 1940.

Sealed tenders will be received at the Office of the Executive Engineer, Sagara-Talguppa Railway, Sagara, up to 3 P.M. on the 3rd February 1940, from Contractors for works in connection with "Constructing Pumpers' Quarters at Talguppa."

2. Tenders should be submitted only in special forms which can be obtained from the Executive Engineer, S.-T. Railway Construction, Sagara, on payment of rupee one being the cost of the form.

3. The tender must be accompanied by a receipt of payment of earnest money of Rs. 200 to the Executive Engineer, S.-T. Railway Construction, Sagara, mentioning the above work, in cash. No cheques will be received.

4. Tenders which give rates "as per estimate" or so much per cent above or below estimate rates will not be considered.

5. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

6. The name of the accepted tenderer will be posted on the Notice Board of the Executive Engineer's Office, as soon as it is approved. No enquiries regarding the acceptance or rejection of a tender will be replied to.

7. Detailed estimates, plans and specifications, conditions of Schedule Agreement may be seen at the Executive Engineer's Office, S.-T. Railway Construction, Sagara, on all working days between 11 A.M. and 5 P.M. When in doubt, the tenderers should always ask for particulars and details.

8. The earnest money (referred to in para 3 above) of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of, while that of the successful tenderer will be accepted as part security for the due fulfilment of the terms of the Agreement.

9. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore State Railway, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves himself the right to reject, without assigning any reason therefor, any or all the tenders or any portion of a tender.

10. The work should be started within a week from the date of acceptance of the Schedule Agreement and should be completed before the end of April 1940, with a guaranteed monthly rate of progress. The whole work should be completed by the 30th April 1940.

11. Within a week from the date of acceptance of the tender, the successful tenderer is required to execute the usual Schedule Agreement, in default of which his tender will be considered as cancelled and the earnest money forfeited to Government.

12. There should be no corrections or erasures in the tender in the rates of items and any corrections made in the rates should be attested to and the number of corrections if any, in each page noted at the foot of the same by the tenderer.

13. Rates once tendered cannot be enhanced on any account. Rates for non-tendered and non-estimated items shall be as per minimum schedule of rates of the Railway Department, or those fixed by the Executive Engineer, after working out data with 10 per cent for Contractor's profit.

14. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any item of work or specification, the decision of the Superintendent, Way and Works, Mysore State Railway, Mysore, shall be final.

15. The accepted tenderer must make his own arrangements in advance for payment of royalties, toll, octroi, etc., in case he quarries stone, earth, kunkar, sand, etc., from Railway, Government or Forest land for use on this work, as this Department will not concern itself regarding the payment recovery of royalty, tolls, octroi, etc.

16. No claims for damages, for delays caused by Officers of the Department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by Departmental Officers, will, however, be considered on the merits of each case.

17. The contract should not be sublet.

Note A.—

The Contractor should at his own cost—

(1) Provide bamboos, rods, stakes, ropes and labour required in setting out the work.
(2) Provide mortar mill and shed to keep materials under cover and also for workmen.
(3) Arrange for protecting work during inclement weather.
(4) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(5) Supply requisite temporary lights, water cisterns, water shoots, coverings to masonry, sieves, parahs, or measures, shoring and other requisite protection during the progress of work.
(6) Supply all water required for work and workmen and shall provide latrines, drainage, etc.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and bailing from excavation and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Wash floor at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

Note B.—

(1) In general, works should be executed as per Marryat's Specifications.

Note C.—

R.M.C. Certificates will be given for cement from Bhadravati, slabs from Kadur or Karadi and Teakwood from Shimoga Town or Tarikere.

Schedule.

Sl. No.	Description of work	Quantity	Unit	Rate
				Rs. a. p.
1	Earthwork excavation for founds	1,219	1,000 C.ft.	
2	Concrete broken stone in cement mortar 1 : 6 : 10	214	100 C.ft.	
3	Laterite in cement mortar 1 : 6	1,305	,,	
4	Laterite in mud	3,135	,,	
5	Archwork in laterite in cement mortar	72	,,	
6	T. W. Doors battened with frames, shutters 1″ thick, handles, hinges, etc., complete	156	S.ft.	
7	T. W. Doors with frames, G. I. shutters, handles, hinges, etc., complete	168	,,	
8	T. W. windows with battened shutters 1″ thick, ¾″ square iron bars fixed at not more than 3″ centres, handles, hinges, hooks, etc., complete	72	,,	
9	T. W. Ventilators with iron bars and glazed shutters and with fittings complete	27	,,	
10	Burnt stone slabs 6″ thick dressed with R.M.C.	86	,,	
11	Teakwood wrought and put up including wood oiling 2 coats	79.07	C.ft.	
12	Roofing with 1st class Mangalore tiles on teak reepers 2″×1″ chunam borders and wind ties, complete.	1,978	100 S.ft.	
13	Supplying and fixing G. I. sheets for valleys including planks ¾″ thick complete	144	S.ft.	
14	Mangalore ridge tiles set in mortar and pointed in cement	117	R.ft.	
15	Supplying and fixing pestle and mortar (stone 2′×2′×2′) with R.M.C. from Kadur	4	Each	
16	T. W. planks 1″ thick	13·5	S.ft.	
17	Flooring with 3″ thick cement concrete 1 : 6 : 10 and plastered in cement ½″ thick	1,070	100 S.ft.	
18	Plastering in cement ½″ thick	460	,,	
19	Plastering in mortar ½″ thick	5,164	100 S.ft.	
20	Pointing in cement	2,133	,,	
21	White-washing 2 coats	5,164	,,	
22	Cement concrete fret work	24	S.ft.	
23	Painting with green lac paint	846	100 S.ft.	

M. R. KRISHNAMURTHI,
Executive Engineer.

STORES DEPARTMENT.

Abstract Notification.

The attention of the public is hereby invited to Notification dated 13th January 1940, published in the *Mysore Gazette*, dated 18th January 1940, on pages 130-131 of Part VI, regarding "Tender sale No. 21 for the purchase of empty Keros ne oil tins and empty steel barrels 40/45 gallons capacity" available up to 31st December 1940, in the Railway Central Stores, Mysore South.

A. VISWANATH,
Controller of Stores.

GOVERNMENT HIGH SCHOOL, CHITALDRUG.

Notice dated 7th January 1940.

It is hereby notified that the unserviceable Typewriter (Remington No. 11, visible), belonging to this High School, will be sold by public auction at 11 A.M. on 3rd February 1940 in the School premises. The auction is subjected to the usual conditions governing such auctions. The machine is open to inspection on any working day between 11 A.M. and 5 P.M. Details regarding the conditions of auction may also be learnt from the Office of the High School.

H. NAGAPPA,
Head Master.

PRIVATE ADVERTISEMENTS.

IN THE COURT OF THE PRINCIPAL SUBORDINATE JUDGE AT BANGALORE.

Miscellaneous Application No. 94 *of* 1939-40.

(1) Nagamma, widow of the late Kuppagal Aiyyappa, Veerashaiva by caste, residing at Bruspet, Bellary Town, (2) Nagappa, adopted son of the late Kuppagal Aiyappa, aged about 10 years, minor by guardian and adoptive mother the 1st petitioner, and residing under her protection .. .. *Petitioners.*

vs.

(1) Seelavantara Muddaniah, son of Gurubasaviah, aged about 60 years, (2) Soogare Mutt Mariswamiah, son of Poniah, aged about 50 years, (3) Meti Doddappa, son of Basappa, aged about 35 years, (4) Shivachennabasappa, son of Doddabasappa, all are Veerashaivas by caste, and residing at Bruspet, Bellary .. .. *Opponents.*

In the matter of the estate of Kuppagal Aiyyappa .. .. .. *Deceased.*

Whereas Nagamma, applicant, resident of Bellary Town, claiming to be the heir of the said Kuppagal Aiyyappa, deceased, has applied to this Court, for a Certificate under Act VII of 1901, to collect debts payable in respect of the estate of Kuppagal Aiyyappa, deceased, resident of Bellary.

Notice is hereby given of the said application and all claimants in the estate of the said Kuppagal Aiyyappa, deceased, are invited to appear in this Court on Friday the 26th day of January 1940 when the petition of the said Nagamma, applicant, will be heard, and the right to the certificate will be determined.

Given under my hand and the seal of the Court, this 15th day of January 1940.

Insolvency No. 37 *of* 1939-40.

Hajee Mahamed Hajee Esa, by Manager, Hajee Hussain Meerut and six others, Old Tharagupet, Bangalore City .. .. *Creditiors (Petitioners).*

vs.

P. M. Ismail Shaib, by P. M. Ismail Shaib, aged about 50 years, Grain Merchant, New Tharagupet, Bangalore City .. .. *Debtor.*

Whereas Hajee Mahomed Hajee Esa and seven others, creditors, have applied to this Court by a petition dated 2nd December 1939, to declare you an insolvent under the Mysore Insolvency Act XI of 1925 and such insolvency petition is admitted, this is to give you notice that the Court has fixed the 3rd day of February 1940 for the hearing of the aforesaid petition.

Dated this 17th day of January 1940.

D. RAGHAVENDRA RAO,
Principal Subordinate Judge.

IN THE COURT OF THE MUNSIFF AT KOLAR GOLD FIELDS.

Insolvency Application No. 28 *of* 1939-40.

Muniswamy, Blacksmith, Jumper Shop, Oorgaum Mines .. .. .. *Petitioner.*

Whereas the petitioner abovenamed has applied to this Court, by a petition dated 30th day of October 1939, to be declared an insolvent under the Mysore Insolvency Act, VI of 1911, this is to give notice that the Court has fixed the 30th day of January 1940 for the hearing of the aforesaid petition and the examination of the debtor. If you desire to be represented in the matter, you should attend in person or by duly instructed pleader.